

Final Design - Public Information Center









Presentation Overview



Project Team



Project Delivery Process



Project Location/Limits



Purpose and Need



Proposed Improvements



Construction Staging



Detour and Parking Impacts



Project Schedule and Construction Cost Estimate



Feedback









Project Team









Mercer County - Bridge Owner and Project Sponsor

NJDOT Local Aid and DVRPC – Design Oversight and Construction Funding

GPI – Engineering Design Consultant









Project Delivery Process

Local Concept Development	Local Preliminary Engineering	Final Design / Right of Way Acquisition	Construction
Purpose and Need Statement	Approved Design Exception Report	Construction Contract Document and PS&E Package	Completed Construction
Data Collection and	Cost Estimates (Final Design ROW	Documentand FS&L Fackage	As-Builts
Environmental Screening Report	and Construction)	Environmental Reevaluations	Update and Finalize Design
Selection of Preliminary Preferred	Approved Environmental	Environmental Permits	Communications Report
Alternative	Document	Acquisition of ROW	Close-Out Documentation
NEPA Classification	Approved Project Plan		
Concept Development Report	Preliminary Engineering Report	Update Design Communications Report	
Create Design Communications Report	Update Design Communications Report		










Project Location Map



Project Location Map - Close up



Purpose and Need

- Purpose is to eliminate structural deficiencies and incorporate operational, safety, and pedestrian access improvements
- Bridge is classified as "Structurally Deficient" due to existing condition
 - Deck rating: 4-Poor
 - Superstructure rating: 3-Serious
 - Substructure rating: 5-Fair
- Sufficiency Rating of 35.7
- While in serious condition and "structurally deficient", this does not imply that the bridge is unsafe for use. It means the bridge must be monitored, inspected and maintained, and possibly rehabilitated or replaced.














Proposed Bridge - Elevation












Proposed Bridge - Typical Sections












Construction Staging



EXISTING TYPICAL SECTION











Architectural Treatments






PROPOSED BRIDGE PARAPET ARCHITECTURAL TREATMENT







PROPOSED PIER WITH ARCHITECTURAL TREATMENT











Proposed Roadway Improvements



Detour and Parking Impacts During Construction



Key Takeaways:

- Eastbound traffic over the Bridge will be detoured during construction. Westbound traffic will be maintained.
- Pedestrian traffic will be maintained in all stages of construction
- Parking impacts at three intersections around the detour route as shown.
- Sporadic full roadway closures (vehicular and pedestrian) will be used during off-peak, nighttime hours to complete construction activities that obstruct access.
- Access to business/driveways will be maintained throughout construction.
- NJ Transit bus stops within the detour limits shown along N Clinton Avenue and E State Street may be temporarily closed or relocated due to construction. Residents that take the bus regularly in these areas will be notified of any changes a minimum of 2 weeks in advance.
- During Stage 2 of construction, the Creekview Drive traffic pattern will be temporarily reversed due to the traffic shift on Lincoln Ave. Normal traffic pattern to be restored upon completion of construction.

Project Schedule and Construction Cost Estimate

Concept Development

Completed: Spring 2018

Preliminary Engineering

Completed: Summer 2022

Final Design

Est. Completion Fall 2025

Construction

Est. Spring 2026 – Fall 2031



Estimated Construction Cost:

\$54 Million Dollars









Public Feedback

If you would like to provide feedback, please visit the following website to leave a question, comment, or statement of support:



www.linavbr.com





For more information contact:

Basit Muzaffar, PE, Mercer County Engineer bmuzaffar@mercercounty.org







